



- NOTE:**
1. PIPE MUST BE PLACED IN A 6" BEDDING OF AASHTO NO. 8 AGGREGATE, AND ALSO HAVE A 12" COVERING OF AASHTO NO. 8 AGGREGATE. AIR TEST MUST HOLD 3 P.S.I. FOR 5 MINUTES.
 2. IF INTERIOR PLUMBING IS NOT ADEQUATELY TRAPPED, AN EXTERNAL TRAP WITH VENT PIPE AND MUSHROOM CAP IS RECOMMENDED PRIOR TO INITIAL CLEANOUT. ADEQUACY OF TRAPPING (TO PREVENT SEWER GAS FROM ENTERING THE HOME) SHALL BE DETERMINED BY CONTRACTOR & HOMEOWNER.

BUILDING SEWER
NOT TO SCALE



369 East Park Drive
Harrisburg, PA 17111
(717) 564-1121
Fax (717) 564-1158
hrg@hrg-inc.com
www.hrg-inc.com

**SCOTT TOWNSHIP AUTHORITY
STANDARD DETAILS**

COLUMBIA COUNTY PENNSYLVANIA

PROJ. MGR. - ENT
DESIGN - ENT
CADD - RSF
CHECKED -
SCALE - N.T.S.
DATE - JAN. 2013

DETAIL NO. D28
SHEET NO. 1 OF 1
PROJECT 005755.0426